

SUPPLEMENTAL / BID BULLETIN NO. 001

TITLE : SERVICE PROVIDER FOR THE ENHANCEMENT OF FIBER BACKBONE AND STRUCTURED CABLING SYSTEM OF DSWD FIELD OFFICE MIMAROPA

ITB NO. : DSWD4B-2025-005

DATE : 4 APRIL 2025

This Supplemental/Bid Bulletin is issued to all prospective bidders announcing the following:

PARTICULARS	REVISIONS/ ADDITIONAL WORKS
<p>1. Item no. III. PROJECT SPECIFICATION A. SCOPE OF WORK</p> <p>1. Fiber Backbone Implementation</p>	<p>Item no.</p> <p>III. PROJECT SPECIFICATION A. SCOPE OF WORK</p> <p>1. Fiber Backbone Implementation</p> <p>1.9 Retermination / Rehabilitation / Installation of Fiber Patch Panels on the following IDFs:</p> <p>1.9.1 Main Data Rack (at least 12-port LC Duplex Patch Panel and accessories)</p> <p>1.9.2 3rd Floor Main Bldg. IDF (Rehabilitation / Retermination of fiber links in the existing 8-port panel)</p> <p>1.9.3 2nd Floor Main Bldg. IDF (at least 4-port LC Duplex Patch Panel and accessories)</p> <p>1.9.4 1st Floor Main Bldg. IDF (at least 4-port LC Duplex Patch Panel and accessories)</p> <p>1.9.5 2nd Floor Admin Bldg. IDF (at least 4-port LC Duplex Patch Panel and accessories)</p> <p>1.9.6 1st Floor Admin Bldg. IDF (at least 4-port LC Duplex Patch Panel and accessories)</p> <p>1.9.7 ARD for Operations Office IDF (at least 4-port LC Duplex Patch Panel and accessories)</p>

<p>2. Item no.</p> <p>III. PROJECT SPECIFICATION A. SCOPE OF WORK</p> <p>2. Structured Cabling Implementation 2.9 Wall mounting of IDF in 2nd Floor Admin Building</p>	<p>2. Item no.</p> <p>III. PROJECT SPECIFICATION A. SCOPE OF WORK</p> <p>2. Structured Cabling Implementation 2.9 Wall mounting of the IDF on the 2nd floor of the Admin Building, with a metal stand support to ensure stability.</p> <p>2.10 Cable layout, cable pulling and termination, and relocation of existing wireless access points to specified locations to ensure an optimal wireless user experience.</p>
<p>3. Item no.</p> <p>III. PROJECT SPECIFICATION C. BILL OF MATERIALS</p> <p>1. Fiber Backbone Implementation</p> <p>a. One Lot of Materials for Fiber Backbone Implementation including but not limited to:</p> <ul style="list-style-type: none"> i. OM4 Fiber Optic Cable - 4 core ii. 1U Fiber Patch Panel - Blank iii. LC SFP/SFP+ Fiber Modules 	<p>3. Item no.</p> <p>III. PROJECT SPECIFICATION C. BILL OF MATERIALS</p> <p>1. Fiber Backbone Implementation</p> <p>a. One Lot of Materials for Fiber Backbone Implementation including but not limited to:</p> <ul style="list-style-type: none"> i. Multi Mode OM4 Fiber Optic Cable - 4 core ii. 1U LC Duplex Fiber Patch Panel and accessories - (at least 4-port for IDFs and at least 12-port for Main Data Rack) iii. LC SFP+ Fiber Modules

This Bid Bulletin shall form part of the bidding documents.

Please be guided accordingly.


KENNETH M. MONTENEGRO
 Chairperson
 Bids and Awards Committee

Please accomplish the portion below and email at procurement.fomimaropa@dswd.gov.ph.

Received from DSWD Field Office MIMAROPA, Supplemental/Bid Bulletin No.1 for the Service Provider for the Enhancement of Fiber Backbone and Structured Cabling System for DSWD Field Office MIMAROPA with Project ID No: DSWD4B-2025-005

RECEIVED BY : _____ DATE: _____
(SIGNATURE OVER PRINTED NAME)

DESIGNATION : _____

COMPANY : _____